



**CITY OF SMYRNA**

**ADDENDUM #3  
FOR  
RFP 17-014**

**COMMUNITY CENTER AV**

November 3, 2016

**OWNER:** CITY OF SMYRNA  
2800 KING STREET  
SMYRNA, GA 30080

**PROGRAM MANAGER:** CROY ENGINEERING, LLC  
200 N. COBB PARKWAY, SUITE 413  
MARIETTA, GA 30062



**TABLE OF CONTENTS**  
**COMMUNITY CENTER AV (RFP 17-014)**  
**ADDENDUM #3**

I. LIST OF ADDENDUM ITEMS

**LIST OF ADDENDUM ITEMS**

**NOTICE TO BIDDERS: THIS ADDENDUM #3 FORMS A PART OF THE REQUEST FOR PROPOSAL 17-014, COMMUNITY CENTER AV PROJECT, AND MODIFIES THE ORIGINAL VERSION AS FOLLOWS:**

**ITEM 1**

RFI #3

1. Bid Bond, what is the % required for the bid bond with this bid? **5%**
2. Is AIA acceptable? **Yes**
3. Due to the small time period remaining (*8 working days prior to bid opening*) subsequent the addendum #2 issue date, is it a possibility the bid opening be delayed a few days to allow participants sufficient time to attain a bid bond and address the remaining topics listed? **No. The bid is scheduled for Wednesday November 9, 2016 at 2:30 P.M. per Addendum #1.**
4. RE: Question 10., Addendum #1 - Do you have the Model number for the Da-Lite 113” screen? **Da-Mat**  
Da-Mat is a Da-Lite surface material only. Are additional screen specifications available?  
**PN: 34516LS**
5. There doesn’t seem to be an audio output card listed for the DM-MD8X8 switcher. Should a Crestron DMC-4K-HDO be included in the proposal? **Output card is required**
6. The Crestron router does not appear to have an audio output to route, to the distributed sound system, is a DMC-4K-HDO required, please clarify? **Yes, the system will require an output card, equipment specified in RFP was basis of design. Contractor responsible for fully functional audio visual system.**
7. Is the Epson model Powerlite Pro 6070W WXGA with resolution the projector necessary for this system design? **Yes, projector model is correct.**
8. Will you accept an the alternate model #KRA914 for the Extron model #XPA1002? **No**
9. Will you accept alternates for the following? **Yes. All cabling shall be plenum rated and supported on 4’ intervals with J-Hooks. Cable ties are also to be plenum rated.**

CABLELABEL	CABLE LABELS
CABLESUPPORT	CABLE SUPPORT ASSEMBLY
PLENUMCABLE S	TRYTON PLENUM CABLE TIES